

Guyana Shore Base Inc.

Technical Specification

Supply and Delivery Supply of Concrete for Expansion, G-Store 2 McDoom, East Bank Demerara.

Quantity	Description	Measurement
560	<p>M30 Concrete (4350 Psi) To be delivered to G Store 2, G City Sublot A *For every 35 CYD (cubic yards) of material, you need to collect 6 cube samples. *The test results for 7-day strength should range between 18-21 MPa (Megapascals). *The test results for 28-day strength should be a minimum of 30 MPa."</p>	m3
100	<p>Blinding - 1500 PSI To be delivered to G Store 2, G City Sublot A Delivery to G Store 2, G City. Supplier to ensure the pump truck is adequately equipped to reach all areas of the foundation for concrete and blinding pouring</p>	m3
660	<p>Supply of Pump Truck to pump supplied concrete "Delivery to G Store 2, G City. Supplier to ensure the pump truck is adequately equipped to reach all areas of the foundation for concrete and blinding pouring. "</p>	m3
1	<p>Supply of slump testing Every delivery of M30 Concrete Slump test results should be between 5-6 inches" "General Notes: *The batching plant must be located within a 310-minute drive by mixer truck, even during rush hour. *The pump truck must have a minimum reach of 38 meters."</p>	