

Guyana Shore Base Inc.

Technical Specification

Supply and Delivery of Partition Walls and Crane Structures at G-Store 2 McDoom, East Bank Demerara.

Quantity	Description
1	<p>Structural frames of identical quality shall be supplied for the partition wall and the two walls required to enclose the Tear Down area. The partition walls will be covered with galvanized and pre-painted corrugated metal cladding, utilizing sheeting with a thickness of 0.5mm.</p> <p>Additionally, a steel framework will be retrofitted to provide support for the overhead crane in the primary work area. The structural steel, designated as Q235B, will undergo treatment of two primer coats followed by a single coat of finish paint.</p>