

**SUPPLY AND DELIVERY OF PRECAST RC PARKING CURBS AT MAIN BASE, GYSBI  
BILL NO.1 - WORKS**

Ref	Description	Unit	Qty	Rate	Amount
2.1	<p><b>A35 EMPLOYER'S REQUIREMENTS: SPECIFIC LIMITATIONS ON METHOD/ SEQUENCE/ TIMING/ USE OF SITE</b></p> <p><b>Site Access:</b> All personnel require the company's approval for acces to the site. Service Providers requiring access shall request access via <a href="https://visit.gysbi.gy/register">https://visit.gysbi.gy/register</a>.</p>	-	-	-	-
2.2	<p><b>E50 Precast Concrete Structures</b></p> <p><b>Precast RC Parking Curbs</b></p> <p>Supply and deliver precast RC parking curbs; in accordance with the Drawings . Each parking curb MUST be casted to a fair faced finish, achieve a minimum compressive strength of 4,000 psi and painted with a primer and 2 coats of Safety Yellow paint.</p> <p>Rate to include for concrete testing, all finishings and delivery of curbs to Main Base, GYSBI or as directed by the Client.</p>	Nr.	35		
	Total (Guy\$)				