



GYSBI_CT	_038_	0000
----------	-------	------

## REQUEST FOR PROPOSALS (RFP)

### FABRICATION AND DELIVERY OF PRESTRESSED CONCRETE PANELS

#### 1. INTRODUCTION

Guyana Shore Base Inc. invites qualified suppliers to submit pricing for the fabrication and delivery of five (5) prestressed concrete replacement panels in accordance with the Prestress Panel Design Drawing - IFP.

#### 2. SCOPE OF SUPPLY

Supplier shall provide all labor, materials, prestressing operations, QA/QC, and delivery required for:

- Five (5) prestressed concrete panels:
- Prestressing strands: per S1.
- Reinforcing steel: per General Notes.
- Embedded components
- Surface finish: Troweled per CS2.
- All formwork, inserts, chairs, spacers, and lifting hardware.
- Delivery to GYSBI site, coordinated with GYSBI.

#### 3. TECHNICAL REQUIREMENTS

Fabrication shall comply with all notes on CS2 and S1, including:

- Concrete Requirements (Ref. CS2 – Concrete Notes)
- Concrete compressive strength: 8,000 psi @ 28 days
- Thorough mechanical vibration and consolidation
- Slump and placement per General Notes
- Panels cast monolithically
- Prestressing (Ref. S1 Details)
- Prestress layout, strand count, and drape per drawing
- Full tension logs required as submittals
- Reinforcement (Ref. CS2 – Reinforcing Steel Notes)
- New deformed billet steel, ASTM A615 Gr. 60
- Minimum development lengths per ACI 318
- Bars tied securely; proper spacers/chairs required
- Dimensional Requirements (Ref. S1)
- All dimensions and conduit/sleeve locations must match drawings precisely
- Any discrepancies to be reported prior to fabrication



GYSBI_CT	_038_	0000
----------	-------	------

## 4. DOCUMENTATION

Supplier must provide:

- Material certificates (cement, aggregates, rebar, strands)
- Concrete mix design for 8000 psi class
- Prestress procedure and tensioning logs
- QC testing results (slump, cylinders, 7-day & 28-day breaks)
- Final inspection/measurement report
- Delivery method statement

## 5. DELIVERABLES

- Five completed prestressed concrete panels
- Complete QA/QC documentation package
- Material certifications and test results
- Delivery to GYSBI

## 6. REQUIREMENTS FOR RFI SUBMISSION DETAILS

- **Date published:** December 11, 2025
- **Deadline for Submission:** January 8, 2026

**All submissions must be provided as separate PDF documents, as outlined below:**

- **Document Attachments** - All submissions must be provided as **separate PDF documents**, as outlined below:
  - **Supplier Business Documents** – Certificate of Incorporation/Business Registration, Local Content Certificate (or proof of application/intention to obtain one). If no LC Certificate is available, please provide details of the company's ownership structure, GRA & NIS compliances, as well as any other relevant documents or certifications.
  - **Technical Proposal** – Required for **RFP** tenders.
  - **Commercial Quotation** – Required for **RFP and RFQ** tenders. Each cost must be presented as a separate line item, such as Item(s) Cost, VAT, Freight/Other Charges, and Transportation/Delivery, etc.
  - **Specification Sheet(s)**: Suppliers are required to provide specification sheet(s) where applicable.
- **Vendor Prequalification Assessment** – As part of the tender process, suppliers are required to complete **GYSBI's Vendor Prequalification Form** using the following link: [SC-FO-011-B: GYSBI Vendor QHSE Pre-qualification Survey Form B](#)



GYSBI_CT	_038_	0000
----------	-------	------

## ➤ Submission & Clarifications

- **Submission Email Address:** [tenders@gysbi.com](mailto:tenders@gysbi.com) with Subject line:  
"FABRICATION AND DELIVERY OF PRESTRESSED CONCRETE PANELS"
- **Clarifications & Queries:** All inquiries must be directed to the same email address listed above.

## 7. DISCLAIMER

Guyana Shore Base Inc. reserves the right to accept or reject any submission at its sole discretion and to proceed with the procurement in any manner it deems fit.

We look forward to receiving your RFP and working with capable suppliers to successfully satisfy our requirements.

### Issued by:

GUYANA SHORE BASE INC. (GYSBI)  
December 11, 2025